



Society of Petroleum Engineers

SPE-227742-MS

Risks and Proposed Mitigations for Deploying Downhole Wireless Controlled Devices, Moving Towards the Digital Oilfield

A. Nelson and M. Konopczynski, TAQA Well Completions, Houston, Texas, USA

Copyright 2025, Society of Petroleum Engineers DOI [10.2118/227742-MS](https://doi.org/10.2118/227742-MS)

This paper was prepared for presentation at the Middle East Oil, Gas and Geosciences Show (MEOS GEO), Manama, Bahrain, 16 – 18 September 2025.

This paper was selected for presentation by an SPE program committee following review of information contained in an abstract submitted by the author(s). Contents of the paper have not been reviewed by the Society of Petroleum Engineers and are subject to correction by the author(s). The material does not necessarily reflect any position of the Society of Petroleum Engineers, its officers, or members. Electronic reproduction, distribution, or storage of any part of this paper without the written consent of the Society of Petroleum Engineers is prohibited. Permission to reproduce in print is restricted to an abstract of not more than 300 words; illustrations may not be copied. The abstract must contain conspicuous acknowledgment of SPE copyright.

The integration of advanced digital technologies into oil and gas operations, particularly through smart completion systems, marks a transformative shift toward the digital oilfield. Traditional downhole monitoring and control methods, which often rely on wired or fiber optic solutions, present substantial limitations, including high operational costs, significant intervention durations, and elevated risks of system failure. The evolution toward wireless-controlled completion devices aims to mitigate these challenges, offering unprecedented flexibility, efficiency, and reliability.

Wireless-controlled downhole devices, including gauges, intelligent control valves, and safety valves, have transitioned from experimental technologies to mainstream solutions due to their demonstrated benefits. These technologies promise significant operational efficiencies, primarily by substantially reducing the need for complex workover interventions. By enabling remote and real-time monitoring and control, wireless technologies dramatically reduce downtime, operational complexity, and associated costs.

However, adopting wireless technologies is not without challenges. Operators and service providers must navigate technological, operational, and organizational risks inherent to deploying wireless systems in challenging reservoir environments. This manuscript aims to rigorously evaluate the deployment of wireless-controlled completion technologies, clearly demonstrating their advantages over traditional wired/cabled systems, identifying potential risks, and proposing actionable mitigation strategies.

Introduction

The integration of advanced digital technologies into oil and gas operations, particularly through smart completion systems, marks a transformative shift toward the digital oilfield. Traditional downhole monitoring and control methods, which often rely on wired or fiber optic solutions, present substantial limitations, including high operational costs, significant intervention durations, and elevated risks of system failure. The evolution toward wireless-controlled completion devices aims to mitigate these challenges, offering unprecedented flexibility, efficiency, and reliability.

Wireless-controlled downhole devices, including gauges, intelligent control valves, and safety valves, have transitioned from experimental technologies to mainstream solutions due to their demonstrated benefits. These technologies promise significant operational efficiencies, primarily by substantially

reducing the need for complex workover interventions. By enabling remote and real-time monitoring and control, wireless technologies dramatically reduce downtime, operational complexity, and associated costs.

However, adopting wireless technologies is not without challenges. Operators and service providers must navigate technological, operational, and organizational risks inherent to deploying wireless systems in challenging reservoir environments. This manuscript aims to rigorously evaluate the deployment of wireless-controlled completion technologies, clearly demonstrating their advantages over traditional wired/cabled systems, identifying potential risks, and proposing actionable mitigation strategies.

Through comprehensive analysis of data collected from real-world deployments, this paper investigates performance metrics such as workover cost reduction, deployment duration improvements, and device durability enhancements. Ultimately, this study highlights critical insights and practical guidance to support operators in effectively deploying wireless-controlled downhole completion devices, thereby advancing the broader industry shift toward digitally enabled, intelligent oilfield solutions.

Technology Background

Downhole completions have traditionally relied on two primary technologies: wired systems for monitoring and control, and hydraulic systems for actuation - particularly in safety-critical components like subsurface safety valves (SSSVs).

In hydraulic-based systems, a control line runs from the surface to the valve, transmitting pressure to open or close the valve. These valves are typically designed to fail as is for ICVs and to fail-safe closed for SSSVs. For SSSVs, when the hydraulic pressure in the control line is lost, a spring or nitrogen charge forces a flapper to shut, isolating the reservoir from the surface. This configuration ensures well integrity in emergency scenarios such as equipment failure or blowout preventer (BOP) activation.

Resetting the hydraulic SSSV flapper often requires reapplication of hydraulic control line pressure from the surface and tubing pressure to equalize the pressure across the flapper. Hydraulic systems may be still operable with very minute control line leaks and physical intervention is usually not required unless the valve fails to respond, however small leaks usually develop into bigger leaks and a costly workover may be needed to pull the full tubing string, repair or replace the SSSV assembly and control line. While these systems have proven reliability, they carry notable drawbacks: complex installations, vulnerability to hydraulic leaks or control line failures, and the high cost of remediation if a malfunction occurs.

Wired completions, on the other hand, use electrical cables permanently installed during the completion phase to connect downhole sensors and actuators to surface equipment. These provide real-time monitoring capabilities but introduce similar risks as hydraulic system - such as cable damage, feedthrough failures, or signal degradation over long distances. Electrical cable devices are intolerant of any degree of leakage of wellbore fluid through connector or seals.

Wireless-controlled downhole devices offer an innovative alternative by eliminating the dependency on continuous physical connections between downhole equipment and surface systems. These devices communicate using acoustic, electromagnetic (EM), or pressure pulse telemetry, with each method tailored to specific well environments and operational objectives. For instance, acoustic telemetry systems transmit data using sound waves through the casing or wellbore fluids, while EM systems use low-frequency signals to penetrate formation layers. Pressure pulse systems modulate bore pressure to send coded signals interpreted by downhole tools.

The primary components of a wireless downhole completion system, whether as part of a completion or retrofit, typically include:

- **Wireless Gauges (WGs):** Used to monitor pressure and temperature in real time. These gauges are often installed on production tubing or casing and are capable of transmitting data to the surface or storing it for later retrieval.

- Intelligent Safety Valves (ISVs): These fail-safe valves can operate autonomously or be remotely opened and closed via wireless signals, enhancing well control in critical safety scenarios without the need for hydraulic control lines.
- Interval Control Valves (ICVs): Enable zonal isolation and flow control without mechanical intervention. Wireless ICVs can adjust flow dynamically based on reservoir conditions or operator commands, improving reservoir management.

Powering these wireless devices presents a unique challenge. Most rely on internal batteries designed for moderate-temperature to high-temperature and high-pressure environments. Battery life becomes a critical design parameter, especially in long-term monitoring or control applications. Advanced power management techniques, including duty cycling and low-power electronics, have significantly extended operational lifespans, with some tools offering several years of autonomous service.

The shift toward wireless completions aligns closely with the broader digital oilfield concept, where data-driven insights drive real-time decision-making. By minimizing the physical footprint and operational complexity of downhole equipment, wireless systems facilitate easier deployment, faster intervention, and reduction in non-production time.

Adoption of wireless-controlled technologies is particularly advantageous in mature fields or wells requiring retrofit solutions. Unlike wired systems, which often demand extensive surface infrastructure and rig-based interventions, wireless devices can be deployed using lightweight intervention methods such as slickline or wireline. This opens the door to economically viable enhancements in fields that might otherwise be bypassed due to unfavorable cost-benefit ratios.

Nevertheless, the performance and reliability of wireless communication in harsh downhole environments remain areas of ongoing development. Challenges include signal attenuation, interference, tool positioning, and temperature extremes. Industry progress in antenna design, signal modulation schemes, and telemetry reliability continues to push the envelope, making wireless completions increasingly robust and dependable.

In summary, wireless downhole technologies represent a significant advancement in completion design and field operations. Their growing adoption is reshaping how operators approach construction, monitoring, and control of oil or gas wells. As the industry continues to pursue automation and optimization, wireless completions are likely to play a significant role in unlocking new efficiencies and capabilities across a diverse range of reservoir conditions.

Methodology

This study is based on a curated set of 11 wireless downhole completion deployments, selected to represent a cross-section of environments, operators, and technologies. All deployments were completed by a single service provider in cooperation with the respective operators using their proprietary wireless technology, ensuring a consistent baseline for analysis. The wells included in the dataset span oil, gas, and multiphase production scenarios, and represent both onshore and subsea operations across multiple global regions. The selection focused on showcasing a mixture of early and recent field deployments to reflect the evolution of implementation practices and performance outcomes over time.

The types of wireless devices evaluated include wireless gauges measuring both pressure and temperature, wireless intelligent safety valves (ISVs), and wireless interval control valves (ICVs). These devices were installed in two primary scenarios: (1) as replacements for failed hydraulic devices such as traditional downhole safety valves or wired devices such as permanent downhole gauges, and (2) as part of new well completion designs where wired solutions were either impractical or less advantageous due to complexity, cost, or deployment constraints.

Each deployment was assessed against three core performance metrics: workover cost reduction, deployment time, and operational durability. The deployment time was based on actual field data

collected at the time of deployment. Deployment time reductions were quantified by comparing wireless intervention durations (typically via slickline or wireline) with historical averages for traditional workover or recompletion operations.

Durability was analyzed using a multi-source estimation approach. In deployments where tools were retrieved, battery rundown tests were used to determine actual remaining capacity. In active deployments, remaining operational life was estimated using proprietary battery life prediction algorithms. These models incorporate temperature-dependent discharge characteristics, tool usage profiles, and historical aging data to forecast remaining service time under expected conditions.

A noted limitation of this study is the variability in operator-supplied data, particularly in cost detail and production outcomes. This introduces challenges in uniformly normalizing the case data across all deployments. Where possible, values were cross-verified against internal operational records or publicly available references.

Despite these limitations, the methodology aims to provide a balanced and representative view of wireless technology performance in real-world oilfield environments. This approach supports an evidence-based discussion of deployment benefits and practical implementation strategies for operators considering similar digital completions.

Case Studies and Analysis

This section presents a detailed look at two representative wireless downhole completion deployments and a summary analysis of all eleven cases. Each case highlights specific device types, operational context, deployment challenges, and performance outcomes. Comparative tables and charts help demonstrate common trends and quantifiable benefits.

Summary of Deployment Scenarios

Case Study	Well Type	Deployment Time (hrs.)	Device Deployed	Location	Reason for Deployment
A	Gas	30	Wireless ISV	Land	Velocity string installed over TRSSSV
B	Gas	20	Wireless ISV	Offshore satellite platform	Control line failure
C	Gas	30	Wireless ISV	Offshore production platform	Existing ISV replacement
D	Gas Condensate/ Light Oil	27	Wireless ISV	Offshore production platform	Control line failure
E	Oil	24	Wireless ISV	Offshore production platform	Control line failure
F	Oil	21	Wireless ISV	Subsea	Control line failure
G	Gas / Water	7	Wireless ISV	Subsea	Control line failure
H	Oil	24	Wireless ICV	Subsea	Provide water shutoff/ interval control with ICV
I	Oil	2	Wireless ICV	Subsea	Provide water shutoff/ interval control with ICV
J	Oil	38	Wireless ICV	Offshore production platform	Installation of ICV to mitigate against premature onset of water breakthrough
K	Water	15	Wireless ICV	Offshore production platform	Deployment of ICV to restrict injection into lower thief zones.

Case Study B – Offshore ISV Replacement

- Well Type: Gas (offshore satellite platform)

- Original Issue: Failure of a wireline retrievable SSSV as a result of blocked control line
- Solution: Wireless ISV deployed via slickline.
- Telemetry: Frequent vitality pulses via pressure pulse telemetry, modeled pre-job.
- Battery Chemistry: Moderate-temperature variant lithium-based battery.
- Deployment Time: 20 hours.
- Workover Avoided: Intervention to replace control line.
- Result: Stable ISV operation with multiple planned test event activations
- Observations: Signal integrity reliable with battery performance aligned with prediction midway through multi-year deployment.

Case Study E

- Well Type: Oil (subsea)
- Original Issue: Well has been offline for 12+ years due to failed control line.
- Solution: Wireless ISV deployed via slickline.
- Telemetry: Periodic vitality pulses via pressure pulse telemetry, modeled pre-job.
- Battery Chemistry: High-temperature variant lithium-based battery.
- Deployment Time: 24 hours.
- Workover Avoided: Intervention to replace control line.
- Result: Stable ISV operation with multiple planned test event activations
- Observations: Production restored. Signal integrity reliable with battery performance aligned with prediction one-third through multi-year deployment.

Cross Case Analysis

Metric	Traditional Average	Wireless Average	Savings Range
Deployment Duration	5-10 days	1 day	60–90% reduction in deployment time
Workover Cost	\$200K-\$35M	~ \$100K	Up to 99.7% cost savings in extreme cases. Typically, 70–95% reduction
Battery Performance	N/A	85-115% target	Predictable life expectancy
Valve/Gauge Failures	15 years average life	Ongoing	Reduced downtime; faster recoverability and real-time monitoring benefits.

To evaluate the economic benefit of wireless-controlled device deployments, workover cost estimations were derived from publicly available benchmarks published by industry and government agencies. Calculations were based on rig rates and typical durations associated with conventional well interventions, with distinctions made between onshore and offshore environments.

For onshore wells, the U.S. Energy Information Administration (EIA) provides capital expenditure estimates based on IHS-Global data. In their 2016 assessment, EIA reports that the average total capital cost per onshore well ranges from \$4.9 million to \$8.3 million, with completion operations alone accounting for \$2.9 million to \$5.6 million per well ([U.S. Energy Information Administration \(EIA\) 2016](#)). It is worth noting that these total capital costs are influenced by unconventional oil and gas wells – long horizontals in shales with multiple fracture stimulation. While this includes the initial completion phase, it provides a basis

for estimating recompletion and workover activity costs. Workover rig day rates for land-based operations typically fall within the \$25,000 to \$50,000 range, depending on region and rig class. When factoring in additional costs for services, consumables, logistics, and personnel, a conservative estimate of \$100,000 per day is used for modeling the economic impact of traditional workovers.

Offshore interventions incur significantly higher costs due to the complexity of operations and the higher daily rig rates. As of 2023, reported daily rates for high-specification jack-up and semisubmersible rigs range from approximately \$177,000 to over \$500,000 per day, depending on rig type, water depth, and contract length (IHS Markit, 2023). Therefore, a typical recompletion operation lasting several weeks offshore can exceed \$10 million in direct rig costs alone, not including associated vessel support and downtime.

These cost benchmarks were used to model potential savings realized using wireless completion devices. For example, deployments performed via slickline or wireline, typically completed in a single-day operation, can avoid the need for a multi-day rig-based workover. As shown in the case studies, interventions using wireless gauges and safety valves consistently eliminated the need for recompletion, resulting in estimated cost savings ranging from hundreds of thousands to multiple millions of dollars per deployment, depending on well environment and depth.

Results and Observations

A detailed comparison across key operational and financial metrics revealed the following:

- Workover cost savings of up to 70–95%, with potential avoidance of multi-million-dollar intervention in many instances.
- Deployment duration reduced from 5–10 days to less than 1 day, representing a 60–90% improvement in efficiency.
- Battery performance within 85–115% of target life, offering predictable service intervals and improved lifecycle planning.
- Valve and gauge reliability enhanced through wireless retrievability, enabling ongoing maintenance without full workover—translating into reduced downtime and increased operational flexibility.

Across the analyzed deployments, the use of wireless tools resulted in substantial cost savings when benchmarked against modeled rig-based workover operations. For onshore installations, typical wireless deployments (often completed via slickline in less than 24 hours) avoided recompletion that would otherwise incur costs in the range of \$300,000 to \$500,000. Offshore interventions showed even greater savings, with estimated avoided costs exceeding \$1 million per deployment in cases where a traditional rig-based approach was no longer unnecessary.

These results are supported by modeled cost assumptions using published industry data. Conservative benchmarks of \$100,000 per day for onshore workovers and \$177,000 to \$500,000+ per day for offshore rigs were used to calculate savings (U.S. Energy Information Administration, 2016 & IHS Markit, 2023). The outcomes reinforce the value proposition of wireless downhole devices, particularly in fields where downtime reduction and operational efficiency are critical.

These comparisons underscore the repeatable benefits of wireless tools: shorter deployment windows, drastically reduced workover costs, and high reliability across reservoir environments. While further data is needed to fully quantify long-term reliability, early results suggest wireless tools are robust and consistent when properly modeled and deployed.

Risks and Challenges

While wireless downhole completion tools offer notable advantages in cost, deployment speed, and operational flexibility, they also introduce a set of technical and operational challenges that must be carefully managed to ensure reliable field performance.

All wireless field deployments evaluated in this paper utilized pulse telemetry for wireless communication. While pulse telemetry has proven to be highly reliable, its performance can be affected by well noise and insufficient pressure amplitude. In one recorded case, a challenging well environment prevented detection of pressure signals through conventional means. However, telemetry detection was successfully restored by leveraging temperature fluctuations in the well fluid as a surrogate indicator of pulse events. These experiences highlight the importance of comprehensive well modeling before deployment to ensure telemetry detectability.

Battery life prediction has generally been accurate in real-world conditions when compared to modeled expectations. However, deviations in tool activity, such as more frequent mechanical actuation or prolonged telemetry activity, can result in faster battery depletion. For instance, each telemetry event briefly reduces flow to transmit a pressure pulse. If a choking assembly encounters debris or partial obstruction requiring multiple clearing cycles, battery consumption can spike unexpectedly. Additionally, higher ambient temperatures accelerate passive battery degradation. This can be mitigated by designing in a redundancy margin with additional battery capacity and tailoring battery chemistry to match well conditions. Lithium sulfuryl chloride performs well between 30°C and 100°C, whereas lithium thionyl chloride is more suitable for wells operating outside that temperature range.

Mechanical failure risks, while rare, include sealing performance and flow obstruction. To mitigate seal failures, tools are designed with multiple redundant seals. For wells producing sand, scale or debris, mechanical obstruction must be anticipated. The capability of the tool to cut through blockages and debris, and the use of debris catchers should be used as standard practice. Fine sand accumulation is another known risk and should be managed through well design considerations such as proper reservoir screens.

Surface-based communication and monitoring rely primarily on tubing head pressure analysis to capture data from the wireless device and production choke modulation to send commands from surface to the wireless device. Integration with surface data acquisition systems that automatically decode telemetry and track routine health signals, such as vitality pulses, can significantly improve real-time responsiveness.

From a deployment standpoint, the learning curve associated with tool configuration is like any new field-deployable system. However, because the installation method is via conventional slickline or wireline, most operators are already familiar with the mechanical aspects of deployment. Nonetheless, transitioning from hydraulic safety valves to wireless equivalents introduces new paradigms in control philosophy, particularly for operators with long experience using hydraulic control lines. The same can be said for operators with experience using wired pressure gauges and cabled safety valves.

Regulatory compliance remains a critical aspect, especially for safety-critical components. Devices such as wireless SSSVs must meet API 14A standards ([American Petroleum Institute, 2021](#)), and more broadly, all downhole tools should align with the recently released API 19E specification ([American Petroleum Institute, 2024](#)). In regions with ATEX or IECEx certification requirements, suppliers must ensure full compliance. Additionally, handling and storing high-energy lithium batteries requires operator awareness of fire risks and safe transport, although many operators are already familiar with battery management from use in other downhole products.

Collectively, these challenges underscore the importance of thorough system qualification, risk assessment, and planning during the adoption of wireless-controlled downhole completion technologies. Addressing these risks through design redundancy, deployment modeling, training, and stakeholder engagement is essential for maximizing the long-term reliability and value of wireless solutions in complex well environments.

Proposed Mitigations and Recommendations

To successfully realize the benefits of wireless-controlled downhole completions, a proactive approach to risk mitigation is essential. The following recommendations address key technical, operational, and organizational risks identified in field deployments.

Telemetry Reliability Planning

Prior to deployment, wells should undergo thorough modeling to determine pulse telemetry suitability. This includes evaluating flowing pressure responsiveness between the deployed tool and the surface, expected background noise, and temperature dynamics. Where telemetry detection is marginal, secondary indicators, such as fluid temperature fluctuations, can be used to support data interpretation. Additionally, tools should be calibrated with conservative signal thresholds and tested in simulated wellbore environments when appropriate.

Battery Life Optimization and Redundancy

Battery life should be calculated based on conservative estimates that incorporate worst-case duty cycles, especially for tools with frequent telemetry activity. A minimum 10–15% energy redundancy buffer is recommended. Battery chemistry must be matched to expected well temperature ranges with consideration of the potential well operating temperature where chemistries overlap. Lithium-based chemistries are exceptionally suitable for moderate and extreme temperature applications. Battery rundown tests on retrieved tools can also help refine future life prediction models. Life prediction models can be further enhanced by feeding back real-world usage data into the models.

Mechanical Robustness and Debris Mitigation

All tools should be designed with multiple sealing barriers and wear-resistant materials suitable for long-term exposure to pressure cycling, solids, and corrosive fluids. Debris-cutting capabilities, self-cleaning mechanisms, or flow-by designs should be considered. Field deployment standards should include the use of debris catchers, and proper reservoir screening should be verified during planning to minimize sand and particulate ingress.

Enhanced Signal Monitoring and Data Integration

Surface acquisition systems should include automated telemetry decoders capable of recognizing pulse sequences, flagging anomalies, and monitoring periodic vitality signals. This enables early detection of signal degradation, improves remote diagnostics, and allows for real-time verification of downhole tool status.

Training and Deployment Support

Operators and wireline crews should receive practical training in wireless tool configuration, telemetry principles, and deployment workflows. Familiarity with software setup, signal interpretation, and response diagnostics ensures smooth operation. Incorporating a deployment checklist and simulation-based validation further reduces human error.

Regulatory Alignment and Safety Practices

Tools intended for safety-critical use must conform to applicable standards such as API 14A ([American Petroleum Institute, 2021](#)) for safety valves and API 19E for broader tool qualification ([American Petroleum Institute, 2024](#)). Battery storage, transportation, and disposal protocols should align standards such as UNC38.3 ([United Nations, as part of the *Manual of Tests and Criteria*, 2021](#)) and IATA guidelines ([International Air Transport Association, 2024](#)). For equipment that is deployed in explosive atmospheres,

ATEX and IECEx compliance is mandatory. Where required, tools should carry relevant certifications to support deployment in regulated jurisdictions.

Operational Feedback Loop

Post-deployment performance should be documented in a standardized format to support continuous improvement. Retrievals should be analyzed for telemetry integrity, battery depletion, and mechanical wear and tear. Data from these assessments can be used to refine tool design, improve life prediction algorithms, and guide future deployment recommendations.

By implementing these mitigations and adopting a structured deployment framework, operators and service providers can maximize the reliability and economic value of wireless-controlled downhole completions while minimizing the risk of degradation in performance or failure in challenging environments.

Conclusions and Future Outlook

The deployment of wireless-controlled downhole completion devices represents a transformative step in the ongoing evolution toward a more digital and responsive oilfield. Through the analysis of these real-world cases, this study has demonstrated substantial operational benefits - most notably, reductions in workover costs, faster deployment timelines, and enhanced durability of downhole tools.

Case studies highlighted how wireless gauges and intelligent control valves can eliminate the need for rig-based interventions, reduce non-productive time, and enable on-demand remote control of well functions. These benefits were especially pronounced in high-cost environments such as offshore operations, where traditional workovers would otherwise incur substantial logistical and financial burdens.

The performance of pulse telemetry has been shown to be reliable when deployment is supported by adequate pre-job modeling, and battery life estimates have proven accurate when coupled with well activity planning. Mechanical reliability and debris mitigation strategies continue to evolve, but with proper system design, including redundant seals, appropriate battery chemistry, and telemetry management, wireless devices are achieving increasingly consistent results.

While challenges remain, including telemetry limitations in noisy wells, the potential for unexpected energy depletion, and the need for operator training, these can be effectively mitigated. The recommendations outlined in this paper, ranging from telemetry modeling to regulatory compliance alignment, offer a roadmap to safer, more efficient wireless deployments.

Looking forward, the integration of wireless devices into the broader digital oilfield infrastructure presents a significant opportunity. Future systems may incorporate edge processing, adaptive signal modulation, and integration with real-time surface automation to enhance remote control and diagnostics. Broader field adoption will also benefit from shared operational learnings, standardization under frameworks such as API 19E, and continued industry collaboration. The industry can further benefit from battery technology evolution that is being driven by other industry sectors.

In conclusion, wireless-controlled downhole tools are no longer experimental - they are a viable and valuable enhancement to well completion strategies. With appropriate planning, training, and system-level thinking, they offer the potential to reshape the economics and flexibility of well operations increasing industry acceptance and adoption.

References

- U.S. Energy Information Administration (EIA), "Trends in U.S. Oil and Natural Gas Upstream Costs," March 2016. <https://www.eia.gov/analysis/studies/drilling/pdf/upstream.pdf>
- Offshore Rig Day Rate Reports, Baker Hughes / IHS Markit, 2023.
- American Petroleum Institute (API), "Specification for Subsurface Safety Valve Equipment", Specification 14A, April 2021.

American Petroleum Institute (API), "Electrical and Electronic Components for Use in Downhole Completion Equipment", Specification 19E, September 2024.

United Nations, as part of the Manual of Tests and Criteria, "UN Manual of Tests and Criteria, Subsection 38.3 – Lithium Battery Testing", *Rev 7*, 2021

International Air Transport Association (IATA), "Lithium Battery Guidance Document", 2024